


ILLAMBAZAR PANCHAYET SAMITY

SCHEDULE FOR CONSTRUCTION OF CONCRETE ROAD AT KHAYERBUNI VILLAGE ADJACENT TO PLAY GROUND UNDER ILLAMBAZAR
G.P. MOUZA-KHAYERBUNI, J.L NO-123, PLOT NO:-692 (FROM PUP LESS FUND).

VIDE NIT NO:- 32/IPS/17-18 DATE:- 06/07/17 (SL. NO.-01)

SL. NO	DESCRIPTION OF ITEM	TOTAL QTY	UNIT	RATE	AMOUNT
1	Box cutting or filling in Road embankment in all sorts of soil including spreading the spoils properly over the flank as necessary or on berm to approximate grade & camber and rolling the sub-grade with power roller to proper camber and grade as per direction and satisfaction of Engineer-in-charge including uprooting and removing plants and jungles when and where necessary. (a) Depth up to 150 mm. sqm Page 238 it 3.16	255.000	sqm	14.4	3672.00
2	Supplying, spreading and consolidating Stone Dust to a depth of 100 mm and above at desired density and C.B.R. as per Specification with power roller to proper gradient and camber including watering as necessary, and lighting, guarding, barricading and making adequate earthen bundh where necessary to protect the edges and curing with water for 2 to 3 days, mending cracks and depressions by rolling where necessary including all incidental charges of roller, cost of fuel & lubricants complete as per specification. Note: Add cost at site of the materials to arrive at the complete rate. The compaction factor is 0.70.(The payment is to be made on the basis of the finished compacted volume of stone dust.) [Page 242, it.4.06]	25.500	cum	1179.82	30085.41
3	Supplying and laying polythene sheet (150 gm/sqm.) over d.p.c. or below flooring or roofing or roof terracing or in foundation or in foundation trenches (P-45, it-13 of p.w.d. bldg.)	255.000	sqm	25	6375.00
4	A. Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement,if any, in ground floor P-12, it-5a	38.250	cum	5299.56	202708.17
5	Providing form work ----- Page 208, it. 11	38.550	sqm	99	3816.45
6	Supplying fitting fixing sign board (900mm x 600 mm) in/c writing matter on it and taking photography of the board all complete.		L.S		1000.00
				Total :-Rs.	247657.03

Unless otherwise mentioned all the rate & nomenclature collected from PWD(bldg & road) sch. w.e.f 01.12.2015



Executive Officer

Illambazar Panchayat Samity

ILLAMBAZAR PANCHAYET SAMITY

SCHEDULE FOR CONSTRUCTION OF CONCRETE ROAD FROM SARUKHAN ADIBASIPARA TO PAYER DHIBARPARA
UNDER ILLAMBAZAR G.P. MOUZA-PAYER, J.L NO-87, PLOT NO:-1950, (FROM MA & ME LESS & BALANCE FUND).

VIDE NIT NO:- 32/IPS/17-18 DATE:- 06/07/17 (SL. NO.-02)

SL. NO	DESCRIPTION OF ITEM	TOTAL QTY	UNIT	RATE	AMOUNT
1	Box cutting or filling in Road embankment in all sorts of soil including spreading the spoils properly over the flank as necessary or on berm to approximate grade & camber and rolling the sub-grade with power roller to proper camber and grade as per direction and satisfaction of Engineer-in-charge including uprooting and removing plants and jungles when and where necessary. (a) Depth up to 150 mm. sqm Page 238 it 3.16	234.000	sqm	14.4	3369.60
2	Supplying, spreading and consolidating Stone Dust to a depth of 100 mm and above at desired density and C.B.R. as per Specification with power roller to proper gradient and camber including watering as necessary, and lighting, guarding, barricading and making adequate earthen bundh where necessary to protect the edges and curing with water for 2 to 3 days, mending cracks and depressions by rolling where necessary including all incidental charges of roller, cost of fuel & lubricants complete as per specification. Note: Add cost at site of the materials to arrive at the complete rate. The compaction factor is 0.70.(The payment is to be made on the basis of the finished compacted volume of stone dust.) [Page 242, it.4.06]	23.400	cum	1179.82	27607.79
3	Supplying and laying polythene sheet (150 gm/sqm.) over d.p.c. or below flooring or roofing or roof terracing or in foundation or in foundation trenches (P-45, it-13 of p.w.d. bldg.)	234.000	sqm	25	5850.00
4	A. Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement,if any, in ground floor P-12, it-5a	35.100	cum	5299.56	186014.56
5	Providing form work ----- Page 208, it. 11	35.550	sqm	99	3519.45
6	Supplying fitting fixing sign board (900mm x 600 mm) in/c writing matter on it and taking photography of the board all complete.		L.S		1000.00
				Total :-Rs.	227361.39

Unless otherwise mentioned all the rate & nomenclature collected from PWD(bldg & road) sch. w.e.f 01.12.2015



Executive Officer

Illambazar Panchayat Samity


ILLAMBAZAR PANCHAYET SAMITY

SCHEDULE FOR CONSTRUCTION OF CONCRETE ROAD AT KHAYERBUNI VILLAGE (NEAR DAB GROCERY SHOP)
UNDER ILLAMBAZAR G.P. MOUZA-KHAYERBUNI, J.L NO-123, PLOT NO:-692, (FROM MA & ME LESS & BALANCE FUND)

VIDE NIT NO:- 32/IPS/17-18 DATE:- 06/07/17 (SL. NO.-03)

SL. NO	DESCRIPTION OF ITEM	TOTAL QTY	UNIT	RATE	AMOUNT
1	Box cutting or filling in Road embankment in all sorts of soil including spreading the spoils properly over the flank as necessary or on berm to approximate grade & camber and rolling the sub-grade with power roller to proper camber and grade as per direction and satisfaction of Engineer-in-charge including uprooting and removing plants and jungles when and where necessary. (a) Depth up to 150 mm. sqm Page 238 it 3.16	150.000	sqm	14.4	2160.00
2	Supplying, spreading and consolidating Stone Dust to a depth of 100 mm and above at desired density and C.B.R. as per Specification with power roller to proper gradient and camber including watering as necessary, and lighting, guarding, barricading and making adequate earthen bundh where necessary to protect the edges and curing with water for 2 to 3 days, mending cracks and depressions by rolling where necessary including all incidental charges of roller, cost of fuel & lubricants complete as per specification. Note: Add cost at site of the materials to arrive at the complete rate. The compaction factor is 0.70.(The payment is to be made on the basis of the finished compacted volume of stone dust.) [Page 242, it.4.06]	15.000	cum	1179.82	17697.30
3	Supplying and laying polythene sheet (150 gm/sqm.) over d.p.c. or below flooring or roofing or roof terracing or in foundation or in foundation trenches (P-45, it-13 of p.w.d. bldg.)	150.000	sqm	25	3750.00
4	A. Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement,if any, in ground floor P-12, it-5a	22.500	cum	5299.56	119240.10
5	Providing form work ----- Page 208, it. 11	22.650	sqm	99	2242.35
6	Supplying fitting fixing sign board (900mm x 600 mm) in/c writing matter on it and taking photography of the board all complete.		L.S		1000.00
				Total :-Rs.	146089.75

Unless otherwise mentioned all the rate & nomenclature collected from PWD(bldg & road) sch. w.e.f 01.12.2015



Executive Officer

Illambazar Panchayat Samity