

**Schedule of work**

**Name of the work: - Construction of concrete road at Chowmondal paca Road to Chowmondalpur Village Road. With in Illambazar Panchayat Samity. [UNDER MA&ME FUND].**

Ref: - NIT No. - 19/IPS/19      Dated: - 26/02/19    [SI No:-01]  
Circulated vide this office Memo No.: -115(23)/IPS/19      Dated: - 26/02/19

SI No	Description of Item	Quantity	Rate(Rs.)	Amount(Rs)
1	Box cutting or filling in road embankment in all sorts of soil in/c spreading the spoils .....as per direction (depth upto 30cm)	228.00 Sqm	14.40/Sqm	3283.20
2	Supplying stone dust in/c loading ,unloading & stacking at sit for 100 mm thick compacted consolidation	22.80 Cum	1527.35/Cum	34823.58
3	Suppling and laying polythene sheet (150gm/sq.m) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches.	228.00 Sqm	24.00/Sqm	5472.00
4	Cement concrete Mix Design -20	34.20 Cum	4920.73/Cum	168288.97
5	Hire and labour charges for side shuttering .....fitting, fixing all complete	22.80 Sqm	93.00/Sqm	2120.40
6	Supplying and fitting & fixing of RCC sign board (900 x 1200 ) incl lettering painting etc and taking photograph all complete as per direction.	800.00	No	800.00
7	Total Amount			214788.15
8	Add GST @ 12%			25774.57
9	Total amount with GST:-			240562.72
10	Add:- Cess @ 1%			2405.62
11	Total amount with GST with Cess			242968.00

Rs.2,42,968.00



Executive Officer  
**Illambazar Panchayet Samity**