

**OFFICE OF THE BLOCK DEVELOPMENT OFFICER  
MURARAI-II DEVELOPMENT BLOCK  
PAIKAR :: BIRBHUM**

**SCHEDULE**

Memo no- 11/MGNREGA/Mrr-II

Dated: 11 /01/2021

Name of the Agency :

Name of the Work-Children park with Pavar block at Block premises.


**Supply of Materials**

Sl. No.	Description	Unit	Rate (Rs)	Total Quantity	Total Amount(Rs)
1	Fine Sand	cum	358	54	19332.00
2	Polythene sheet (150 gm per sqm)	kg	70	54	3780.00
3	Stone aggregate below 40mm nominal size	cum	374.5	8.64	3235.68
4	Stone Aggregate(single size):20 mm nominal size	cum	566	8.64	4890.24
5	Stone aggregate 40mm nominal size and above	cum	374.5	23.4	8763.3
6	Portland Cement	tonne	5717	8.1	46307.70
7	Stone aggregate (single size) 40 mm nominal size	cum	551	23.4	12893.4
8	Loading unloading & stacking Sand/ stone aggregate (less than 40mm nominal size)	cum	77	8.64	665.28
9	Coarse Sand	cum	536	16.92	9069.12
10	Loading unloading & stacking stone aggregate (above 40mm nominal size)	cum	83	23.4	1942.20
11	Coloured inter locking C .C.paver Block	sqm	850	360	306000.00
12	Silver sand	cum	800	5.4	4320.00
13	Worksite facilities/Creche/drinking water/first aid	no	1	4110	4110.00
14	Display Board	No	3562	1	3562.00
<b>Total Amount :</b>					<b>428870.92</b>

Rupees Four lakh twenty eight thousand eight hundred seventy and ninety two paise

  
Technical Assistant

Murarai-II Development Block  
Paikar, Birbhum

  
79/01/2021  
APO

Murarai-II Development Block  
Paikar, Birbhum

  
P.O & B.D.O

Murarai-II Development Block  
Paikar, Birbhum