

**OFFICE OF THE NANOOR PANCHAYAT SAMITY
NANOOR ★ BIRBHUM**

TENDER NOTICE: NIT no- 08/NPS/2020-21,

Dated: - 22.01.2021

Sealed tenders are being invited from the bonafied / resourceful contractor/ unemployed engineers co- operative as well as labour co-operative as per current approved base of ARCS, Birbhum/ enlisting contractor of Engineering Department of the Government having experience in same nature of work for the following works, details of which are mentioned below:-

Details of works:-

Sl No	Name of the work	Amount put to tender (Rs)	Earnest Money (Rs)	Credentials	Cost of Tender Paper (Rs)	Time of Completion	Remarks
1	Construction of Community Toilet at Palitpur BusStand of Thupsara GP within Nanoor Panchayat Samity Under head 15th CFC	383831.00	11515.00	230299.00	1200.00	60 days	
2	Construction of Community Toilet at Banagram BusStand of Jalundi GP within Nanoor Panchayat Samity Under head 15th CFC	383831.00	11515.00	230299.00	1200.00	60 days	
3	Construction of Concrete road and Cycle Stand at SI of School Nanoor Circle at Basapara of Thupsara GP within Nanoor Panchayat Samity Under head 15th CFC	484235.00	14527.00	290541.00	1500.00	30 days	
4	Construction of Community Hall at Madhudanga of Daskalgram Kareya II GP within Nanoor Panchayat Samity Under head 15th CFC	485335.00	14560.00	291201.00	1500.00	60 days	

Date & time for dropping tender paper : **02.02.2021 up to 2.00 pm**

Tender paper may be accepted through courier service up to **02.02.2021 up to 2.00 pm**

Venue of dropping tender papers: -

- 1) At the office of Nanoor Panchayat Samity.
- 2) At the office of the Sub-Divisional Officer, Bolpur, Birbhum

Date & Time of opening Technical bid : **02.02.2021 up to 3.00 pm** at the Office of Nanoor Panchayat Samity

Date & time of opening of Financial bid : **02.02.2021 at 3.30 pm** at the Office of Nanoor Panchayat Samity

The tender paper along with schedules is available in the Birbhum District website having the following links:-

http://birbhum.gov.in/Tenders/tenders_new.htm and <http://103.249.37.130/tender>


1. The tender paper consists of two parts. Form-A-Technical Bid, Form-B-Financial Bid. Photocopy of all relevant papers(**Original documents may be submitted on demand at the time of opening of tenders**) mentioned in **check list of Form-A** have to be enclosed with Form-A in a sealed envelope and the Form-B is to be submitted in a separate sealed envelope both Form-A and Form-B and to be submitted in a single sealed envelope and it should be addressed to Executive Officer/B.D.O, Nanoor Panchayat Samity/ Nanoor Dev. Block, Nanoor, Birbhum, Pin-731301, Ph. No- 03463-241342, Fax- 03463-241342, e-mail-bdonanoor@gmail.com
2. All the sealed cover should be superscribe by name, sino of work as well as mentioned the Form A or Form B.

Terms and Conditions

- 1) **Time is the essence** of contract. The successful contractor must complete the work within the stipulated time. No extension of time will be allowed except in special cases. If any contractor fails to complete the work within the stipulated time the work order issued in his favour will be cancelled without assigning any reasons. The excess expenditure if any due to such a step will be recovered from the unpaid bill/ security deposits of the tenderers. This is apart from any other penal measure the undersigned may take including blacklisting of contractors and forfeit of earnest money.
- 2) **Earnest money and Cost of Tender Paper noted** against the name of work will have to be deposited in the form of **ECS MODE(through NEFT/RTGS) in ICICI BANK (Bolpur Branch)**
Account No:-089501000922 IFSC Code- ICIC0000895.
in favour of the undersigned.
The earnest money will be converted in to security money after acceptance. Balance 7.5% security money will be deducted from the Bill. Security money will be released as per norms.
- 3) **The rate should** be quoted in percentage both in figures and words.
- 4) **Incomplete tender will** be summarily rejected. The successful tenderer will have to execute a formal agreement on a NJS of Rs. 10/- before issue of work order.
- 5) **Audit report of** last financial year will have to be submitted in case of Engineers Co- Operative and Labour Co- Operative. Credential of similar type of works will have to be produced in case of Engineers Co- Operative and Labour Co-Operative.
- 6) **All works will** be have to be done according to specification and drawing approved by the authority and as per direction of the S.A.E in charge.
- 7) **No consumable material** will be supplied to the agency for any work from the office of the undersigned. Agency will be responsible for producing all materials required for proper execution of the work in his own cost.
- 8) **Bitumen will be** supplied by the contractor with his own arrangement subject to submission of valid document of I.O.C.
- 9) **For construction of** Black top road power roller of 8-10 ton, hand roller, miller mixture, spot mix plant of 3-5 ton/ hour capacity must be arranged by the contractor on his own cost.
- 10) **All rates shall** be included of all charges, royalty, toll charges, carriage etc.
- 11) **Before starting of** work the worksite must be clean and dressed by cutting all sorts of jungle, shrubs etc. for which no extra payment will be made.
- 12) **Against NIT no:- 08/NPS/2020-21, Dated:-22.01.2021** each contractor can submit in all serial no of tender document to the office of the undersigned.
- 13) **The successful tenderer** will have to start the work within 07 days from the date of issue of work order after execution of the formal agreement and will have to complete within stipulated time.
- 14) **Acceptance of lowest** tender is not obligatory and the undersigned reserves the right to accept or reject any or all tenders without assigning any reason what so ever and also to split up the tendered work to more than one contractor for the interest of scheme execution.
- 15) **Amalgamation of un- employed** Engineers Co- Operative and Labour Co-Operative in any form should not be allowed towards counting of eligibility in participation of tender.
- 16) **GST/IT/Royalty /Cess** at the prescribed rate will be deducted at source. The notice shall perform part of terms and condition of tender and tenderer shall be bound to abide by them.
- 17) **Before submission of** tender, the contractor must visit the work site to judge the local condition from all corners and no plea/complain about the site will be entertained after wards. It will be assumed that the agency offered the tender rate after reviewing entire position of the work site.
- 18) a) **Separate tender should** be submitted in similar way for each work or group of work.
b) **Before submitting tender,** the tenderer must get his signature attested on the contract form by witness failing which his tender liable to be rejected.
- 19) **All working tools** and plants and implements required for the work are to be arranged supplied by successful tenderer at his own cost.
- 20) **The successful tenderer** will have to abide by the provision of West Bengal Contract Labour (Regulation and Abolition of Rules 1972) as will be enforced from time to time. If no labour license is obtained and produced by the contractor, payment will be liable to be withheld.
- 21) **If the last date** of submission of tender is declared as holiday the tender will be received on the next day as usual time.

- 22) **Claim for idle labour** from contractor will not be entertained under any circumstances. No claim will be entertained for any increase in railway freight and market price.
- 23) **The tender received** after the due date and time and any change in quotation after opening of the tender will be out rightly rejected. The Office will not be responsible for the loss of tender form or the delay in the postal transit.

The undersigned reserve the right to accept or reject any or all the tenders or to split up the work between more than one tenders without showing any reason thereof.



Executive Officer
Nanoor Panchayat Samity
Nanoor, Birbhum


Memo no:- (26)/NPS/2020

Dated:-22.01.2021

Copy forwarded for information and with a request for wide publicity to:-

- 1) The District Magistrate, Birbhum, Suri.
- 2) The A.E.O, Birbhum Zilla Parishad, P.O:- Suri, Dist, Birbhum
- 3) The Sub- Divisional officer , Bolpur , Dist, Birbhum
- 4) The District Informatics Officer , NIC, Suri, Birbhum. With a request to upload this notice to official Website of Birbhum district (www.birbhum.gov.in)
- 5-8) The Sabhapati / Sahakari Sabhapati / Karmadakshya, P. K.O.P.S.S / Karmadakshya, S.S.O.T.S.S of Nanoor Panchyat Samity
- 9-11) The Junior Engineer, (B.P/ W.R.D.D/RWP)
- 12) The Post Master ,Nanoor, Dist, Birbhum
- 13) A.& H.C , Nanoor Dev. Block
- 14) The Cashier cum Store Keeper ,Nanoor Panchayat Samity
- 15-25) To the Pradhan(All).
- 26) Office Notice Board


Executive Officer
Nanoor Panchayat Samity
Nanoor, Birbhum



OFFICE OF THE NANOOR PANCHAYAT SAMITY
/ BLOCK DEVELOPMENT OFFICER

TENDER FOR SUPPLY MATERIALS/LOCAL WORKS
From- A(Technical Bid)

(Approved in the meeting ASUOPSS meeting dated 20.02.2016)

PRICE

- | | |
|---|--|
| 1. Estimated Cost/Amount of Tender exceeding up to Rs. 1, 00,000/- | Rs. 300/- |
| 2. Estimated Cost/Amount of Tender exceeding Rs.1, 00,000/-& up to Rs. 2, 00,000/- | Rs.600/- |
| 3. Estimated Cost/Amount of Tender exceeding Rs. 2, 00,000/-& up to Rs. 3, 00,000/- | Rs. 600/- |
| 4. Estimated Cost/Amount of Tender exceeding Rs.3, 00,000/- & above | Rs 900/- plus proportionate increase of Rs 150/- for every Rs 50,000/- |

- Name of the Supplier/contractor _____
Farm/Concern: _____

- Name of work: _____

NIT No: _____ . SI No: _____

- Amount put to Tender: _____

General Rules and Directions

1. The tender paper consists of two parts. Form-A-Technical Bid, Form –B-financial Bid. All relevant papers mentioned in check list have to be enclosed with Form-A and in a sealed envelope and the Form-B is to be submitted in a separate sealed envelope both Form-A and Form-B and to be submitted in a single sealed envelope and it should be addressed to Executive Officer/B.D.O, Nanoor Panchayat Samity, Nanoor, Birbhum, Pin-731301, Ph. No- 03463-241342, Fax- 03463-241342.
2. The Tender Paper completed in all respect should reach this office within the date & time mentioned in the Notice Inviting Tender. Incomplete and defective tenders would be straight-way rejected.
3. In the event of the Tender being submitted by a farm it must be signed separately by each member thereof or in the event of the absence of any partner, it must be signed on his behalf by a person holding Power of Attorney authorizing him to do so.
4. Photocopy of valid PAN card, P.Tax and VAT registration certificate should be submitted along with the Tender paper. Original certificates have to be produced on demand.
5. Cost of tender paper should be deposited along with tender paper in a separate Bank Draft in favour of Executive Officer/ B.D.O
6. The amount of Earnest money will be 2% or 2.5% of the estimated cost. The Earnest Money should be deposited along with the tender paper in the form of a separate Bank Draft in favour of Executive Officer, Nanoor Panchayat Samity/Block Development Officer ,Nanoor dev. Block , payable at Bolpur/ Nanoor as applicable.
7. @10% of the bill amount shall be deducted from the final bill as Security Money, if necessary, and may be released after the security period of six months of the work is satisfactorily completed.
8. 1.00% Income Tax, 5 % sales tax or 3% VAT shall be deducted from the Final Bill. This rate may vary as per Govt. Order.
9. The accepting authority reserves the right to reject all the Tender without assigning any reason any thereof and it will not be bound to accept either the lowest tender or any of the tenders.

CONDITIONS OF CONTRACT

The person whose Tender may be accepted shall, before the date fixed for commencing the work make a declaration on Non-Judicial Stamp Paper worth Rs. 10/ that he shall abide by all the conditions of the contract.

All damages payable by the contractor under the terms of his contract may be deducted by the Nanoor Panchayat Samity from or paid by sale of a sufficient part of his earnest money / security deposit or from the interest of such Govt. security or from any other sums due or which may become due by the Nanoor Panchayat Samity.

The contractor is to deliver the materials on or before the dates mentioned in the tender, failing which he shall be subject to pay 1% of the total amount of the contract for every day not exceeding ten days that he shall exceed his time, as and for liquidated damages.

In every case in which the payment or allowance mentioned in clause 4 shall have been incurred for ten consecutive days, the Authority shall have the power either to annul the contract altogether, or to have the supply completed without further notice at the contractors' risk and expense as the Authority may deem best suited to their interest and the contractor shall have no claim to compensation for any loss that he may incur in any way.

If the contractor shall be hindered in the supply of the materials so as to necessitate an extension of the time allowed in this tender, he shall apply in writing to the Executive Officer/ B.D.O, Nanoor Panchayat Samity/ Nanoor Development Block who shall grant it in writing if reasonable grounds have been shown for it, and without such written authority, the contractor shall not claim exemption from the time liable under clause 4.

The contractor shall give notice to the Executive Officer/ B.D.O, Nanoor Panchayat Samity/ Nanoor Development Block /SAE-in charge of the work, about his intention of making delivery of materials and on materials being approved receipt shall be granted to him by the authority and no materials will be considered as delivered until so approved.

On the completion of the delivery of materials, the contractor shall be furnished with a certificate to that effect but the delivery will be not considered complete until the contractor shall have removed all rejected materials (if any) and shall have the approved materials stacked or placed in such position as may be pointed out to him.

Payment will be made to the extent of one-tenth the quantity delivered during each month. But all such payments made shall be considered as payments on account to be covered by the final bill for the complete supply.

The materials shall be of the best description and in strict accordance with the specification. The contractor shall receive payment for such materials only as are approved and passed by the SAE-in-charge.

In the event of the materials being considered inferior to that described in the specification the contractor shall, on demand in writing, forthwith remove the same at his own charge and cost, and in the event of his neglecting to do so within such period as may be deemed fit by the Technical Authority, that officer may have such rejected materials removed at the contractor's risk and expense, the expense incurred being liable to be deducted from any sums due or which may become due to the contractor.

If the contractor or his work people break or deface any building/road/fence/enclosure/grass land/cultivated land he shall repair/make good the same at his own expense, and in the event of his refusing or failing to do so the damages shall be repaired at his expense the Executive Officer who shall deduct the cost from any sums due or which may become due to the contractor.

The contractor shall supply at his own expense all tools, Plants, implements required for due fulfillment of his contract, and the materials shall remain at his own risk till the date of final delivery, unless it shall have been in the meantime removed for use by the SAE-in-charge.

The contract shall not be sub-let without prior written permission from the authority concerned. In the event of the contractor sub-letting his contract without such permission, he shall be considered to have thereby committed a breach of contract, and his security deposit shall be forfeited and shall have no claim for any compensation for any loss that may accrue from the material he may have collected or engagement entered into.

The decision of the Tender Committee shall be final, binding and conclusive on all questions.

Supplier / contractor will be fully responsible for guarding the materials till those are fully consumed. No measurement will be taken until 60% supply of work each completed.

Signature of Tenderer

Should this tender be accepted, I/We do hereby agree abide by and fulfill all the terms of the above specification and all the conditions of contracts annexed hereto, or in default to forfeit and pay to the Nanoor Panchayat Samity the penalties or sums money mentioned in the said conditions.

Dated:

Tenderer

Signature of the Witness to the Tenderer: _____

Address: _____

(For Office use only)

Check List:

1. PAN Card: Yes/ No
2. IT return : Yes/ No
3. GST Registration Certificate: Yes/ No
4. Credential Certificate with work order: Yes/ No
5. Bank Draft for Tender Paper Cost: Yes/ No
6. Bank Draft for earnest money: Yes/ No
7. Audit report for last financial year: Yes/ No
(Applicable for engineers & Labour Co- operative only)

8. Approved current list of ARCS, (Applicable for Engineers & labour Co- operative) only

As per documents submitted by the tender and after verification of the same it has been found that the tender is recommended as technically qualified / disqualified.


.....
(Signature of S.A.E)

Signature of Officer & Members of Tender Committee:

- 1.
- 2.
- 3.
- 4.
- 5.
- 6.

Accepted / Rejected

Signature of Executive Officer/ B.D.O


Signature of the Issuing Authority

**OFFICE OF THE NANOOR PANCHAYAT SAMITY
/BLOCK DEVELOPMENT OFFICER
TENDER FOR SUPPLY MATERIALS/LOCAL WORKS
From- B (Financial Bid)**

Note:- The schedule for the respective work must be enclosed herewith.

❖ Name of Supplier/ Contractor : _____
❖ Farm /concern : _____
❖ Name of work : _____
NIT No _____ SI no _____
❖ Amount put to Tender : _____

TENDER FOR WORKS

I/ We hereby tender for the execution for the Nanoor Panchayat Samity of the work specified in the under written memorandum within the time specified in such memorandum at the rates specified there in, and in accordance in all respects with the specification, designs, drawings and instructions in writing and in all other respects in accordance with such conditions so far as

MEMORANDUM

i. Name of the Work : _____
ii. Amount put Tender : Rs. _____
iii. Earnest Money : Rs. _____ Vide Draft no. _____
iv. Tender Paper cost : Rs. _____ Vide Draft no. _____
v. Time allowed for the work from date of written order to commence : _____
vi. Rate offered on Percentage Basis (both in figure &word) : _____
AT PAR the schedule rate.
I) _____% less then the schedule rate.
II) _____% above then the schedule rate.

Signature of Tenderer

Should this tender be accepted, I/We do hereby agree abide by and fulfill all the terms of the above specification and all the conditions of contracts annexed hereto, or in default to forfeit and pay to the Nanoor Panchayat Samity the penalties or sums money mentioned in the said conditions.

Dated: _____
Signature of the Witness to the Tenderer: _____
Address: _____

Tenderer

Signature of Officer &Members of Tender Committee Present at the time of opening:

- 1.
- 2.
- 3.
- 4.
- 5.
- 6.

Schedule for Construction of Community Toilet at different GP within Nanoor Panchayat Samity Under head 15th CFC

SI no.	Description of Items	Total Qnt.	Unit	Rate	Amount
1	Earth work in excavation in foundation trenches or drain in all sorts of soils (including mixed soil) the item includes necessary trimming the side of trenches leveling dressing and ramming the bottom, bailing out water as required complete. Depth of excavation not exceeding 1.5 mtr.	7.99	cum	Rs. 119.27	953.00
2	Filling in foundation or plinth by silver sand in layers not exceeding 15cm saturated with water ramming complete including the cost of supply of sand	8.93	cum	Rs. 572.55	5113.00
3	Single layer brick flat soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints.	24.67	sqm	Rs. 266.00	6562.00
4	Cement concrete with graded stone ballast(40mm size excluding shuttering) in ground floor (1:3:6)	1.50	cum	Rs. 4,105.50	6158.00
5	Ordinary cement concrete with M20 grade (1:1.5:3) with graded stone chips 20mm down excluding shuttering and reinforcement at ground floor as per IS 456 2000 Pakur / Chandil variety	8.20	cum	Rs. 4,976.83	40810.00
6	Hire and labour charges for shuttering with centering and necessary staging upto 4m using approved props of slab beam column lintel curve or straight including fitting fixing and striking out after completion of works.)with out prop	49.92	sqm	Rs. 205.00	10234.00
7	ii)with prop	21.07	sqm	Rs. 328.00	6911.00
8	Brick work with 1st class bricks in cement mortar 6:1(i) foundation and plinth	2.47	cum	Rs. 4,197.70	10368.00
9	Brick work with 1st class bricks in cement mortar 6:1(ii) in superstructure	0.25	cum	Rs. 4,420.70	1105.00
10	125mm thick brick work with 1:4 mortar	56.94	sqm	Rs. 584.47	33280.00
11	75mm thick brick work with 1:4 mortar	4.3	sqm	Rs. 411.29	1769.00
12	Plaster (in wall, floor etc.) with sand and cement mortar including rounding off or chamfering corners as directed and racking out joints or roughening of concrete surface including throating, noising and drip courses where i) With 4:1 cement mortar 10mm thick	19.18	sqm	Rs. 119.53	2293.00
13	ii) With 6:1 cement mortar 20mm thick	114.52	sqm	Rs. 149.71	17145.00
14	iii) With 1:6 cement mortar 15mm thick	82.88	sqm	Rs. 132.53	10984.00
15	Neat cement punning on plaster surface Ground floor	79.88	sqm	Rs. 32.74	2615.00
16	Reinforcement for reinforced concrete work in all sorts of structure in/c distribution bars, stirrups, hinders etc. in/c supply of rods, initial straightening and removal of loose rust (if necessary) cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. In ground floor	0.51	MT	Rs. 53,015.07	27038.00
17	Artificial stone in floor, dado, stair case etc. with cement conc. (4:2:1) with stone chips laid in panels as directed with topping made with ordinary or white cement and marble dust in proportion 2:1:1 in/c smooth finishing and rounding off corners and in/c application of cement sluvy before fore flooring works using cement @ 1.75Kg/Sqm all complete in/c all materials and labour (25mm thick)	15.69	sqm	Rs. 240.02	3766.00
18	MS or VI ornamental grill of approved design joints, continuously welded with MS, VI flats and bars for window s railing etc. fitted and fixed with necessary screws and lugs in ground floor. Grill weighing @ 16Kg./M2	0.58	qtl	Rs. 9,888.00	5735.00
19	Supplying, fitting and fixing windows and ventilators with or without integrated grills conforming to IS 1038-1975 and manufactured from rolled steel sections conforming to IS 7452-1974 with non-frictionprojecting type, box type hinges, glazing clips, lugs locking bracket, handle plate etc, including hoisting in position, straightening if required, fixing lugs in cement concrete (1:2:4) with stone chips 20 mm down cutting holes and mending good damages to match with existing surface complete in all respect excluding glazing. In G Floor. Flash butt welded windows and ventilators (b) Openable steel windows as per IS sizes with side hung shutters and horizontal glazing bars. [The extra rate admissible for the openable portion only] (iii) Centre hung ventilators as per I.S. sizes 580 mm.	1.62	sqm	Rs. 1,663.00	2694.00

SI no.	Description of items	Total Qty.	Unit	Rate	Amount
SI no.	Description of items	Total Qty.	Unit	Rate	Amount
20	Supplying fitting and fixing in position approved P.V.C. door frame (Matt finish) made of extruded P.V.C. multichamber hollow section having dimensions 60mm x 50mm x 2mm (+/-0.2mm), horizontal section will be joined with vertical section by galvanised steel screws after inserting two number steel brackets as reinforcement making suitable space for placing hinges, one steel tube 40mm x 20mm x 1.20 mm will be inserted on one full vertical side of the frame (hinge side) as reinforcement, the frame will then be fixed in the opening with the help of P.V.C. expandable fastener/wooden girdles and galvanised steel screws including cost of all materials and labour, hire charges of tools and appliances, carriage of all materials, taxes and all other incidental charges complete.	19	cum	Rs. 279.00	5301.00
21	Supplying fitting and fixing P.V.C. door shutter of approved quality & shade in position, the style & rail of the P.V.C. door shutter will be made of rigid P.V.C. multichamber hollow chamber of 59 mm x 30 mm section with 2.0 mm (+/-0.2 mm) wall thickness. Horizontal & vertical section shall be fixed to each other by self tapping screws and 1 solid polycarbonate or M.S. galvanised tubular 'L' shaped bracket 100mm x 200mm in each corner of the shutter frame for placing hinges. Polymer based multichamber hollow section of 120 mm x 30mm with 2.0 mm (+/-0.2 mm) wall thickness will be fitted in the middle, reinforced by solid polymer bar of 200 mm long at both ends and screws from both sides as lock rail. The section frame will then be fitted in by PVC panels of size 100 mm x 25 mm with wall thickness of 1.2 mm (+/-0.2 mm) and 2 nos. of 6 mm dia bright rod will be inserted horizontally with both side check and nut system and stretchers where fixing of hinges / hasp bolt / tower bolt / door ring are required to be strong enough to with stand wear and tear. The rate is inclusive of cost of all materials, labour, and hire of tools and plants and appliances/c	6	sqm	Rs. 2,127.00	12762.00
22	Supplying fitting and fixing Onssa pattern water closet in white glazed vitreous chinaware of approved make in position complete excluding 'P' or 'S' trap (excluding cost of concrete for fixing) (i) 580 mm X 440 mm	2	no	Rs. 1,613.00	3226.00
23	Supplying fitting and fixing 10 ltr. PVC low down cistern conforming to I.S. specification with PVC fitting complete	2.00	no	Rs. 1,015.00	2030.00
24	Squaring plate with integral flushing with white vitreous chinaware of with	2	no	Rs. 881.00	1762.00
25	Flat back unglazed vitreous chinaware of approved make wooden block complete 465X355X265mm	2	no	Rs. 945.00	1890.00
26	supplying fitting fixing unglazed vitreous chinaware of approved make (i) poly there flush pipe	2.00	each	Rs. 155.00	310.00
27	Supplying fitting and fixing Half round channel with or without outlet as required set in cement concrete (6:3:1) with jhama chips complete. (ii) 600 mm X 150 mm (b) White vitreous chinaware	4.00	m	Rs. 138.00	552.00
28	Supply UPVC Pipes (B-type) & fittings conforming to IS 13592-1992 110mm dia	9.00	m	Rs. 292.00	2628.00
29	UPVC Fittings 110mm dia Plain Tee	5	each	Rs. 85.00	425.00
30	UPVC Fittings 110mm dia Plain Y	4	each	Rs. 206.00	824.00
31	UPVC Fittings 110 mm dia Band 87.5 degree	6	each	Rs. 120.00	720.00
32	Pipe Clip 110mm dia	20	nos	Rs. 21.00	420.00
33	Wash basin vitreous china of approved make in position on 75X75X75mm wood block and CI brackets painting of CI brackets 550X400mm size	2.00	no	Rs. 1,383.00	2766.00
34	Supplying fitting fixing approved brand PVC waste pipe with PVC coupling at one end. Fitting fixing with necessary complete, 900mm long	2.00	no	Rs. 75.00	150.00
35	Supplying fitting fixing approved brand PVC Connector white flexible with both ends coupling. Fitting fixing with necessary complete, 15mm dia 600mm long	2.00	no	Rs. 107.00	214.00
36	Construction of septic tank of different capacities of approved drawing with 1st class brick work with cement mortar 4:1 including two 5mm dia manhole cover of approved make supplied fitted and fixed in the top slab with necessary fittings 19mm thick cement plaster 4:1 with flooring is to be done with admixture of water proofing compound @ 5% by weight of cement complete in all respect as per	1	no	Rs. 31,778.00	31778.00
37	Supplying of PVC water storage tank of approved quality with closed top with lid multilayer 1000ltr	1.00	nos	5128.00	5128.00

SI no.	Description of Items	Total Qnt.	Unit	Rate	Amount
38	Labour for hoisting PVC tank upto 1st floor	1.00	nos	96.00	96.00
39	Labour for punching hole in PVC tank	4.00	nos	19.00	76.00
40	Supplying fitting and fixing PVC pipes with all necessary accessories specials viz socket bend, tee, union, cross, elbow, nipple, long screw, reducing socket, tee, short piece etc. fitted with holder bats clamps all complete				
	i. 15mm dia medium pipe	20	m	101.00	2020.00
	ii. 20mm dia medium pipe	20	m	129.00	2580.00
41	Supplying, fitting and fixing bib cock /stop cock of approved make and brand(EMCO/ATLAS) 15 mm	10	no	89.00	890.00
42	Supply of UPVC pipes (B Type) & fittings conforming to IS-13592-1992 110 mm dia	2	m	Rs.427.00	854.00
43	White washing with any shed with strainer as required including cleaning and smoothening the surface thoroughly.	72.58	sqm	Rs. 20.01	1452.00
44	Decorative cement base paint to external surface two coats including one coat of cement primer outer wall	81.43	sqm	Rs. 49.00	3990.00
45	Priming one coat on timber, plastered or on steel or other metal surface with synthetic enamel/oil bound primer of approved quality including smoothening surfaces by sand papering etc.	5.22	sqm	Rs. 29.00	151.00
46	Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using approve putty etc. on the surface. On steel surface two coats with any shape except white.	5.22	sqm	Rs. 72.00	376.00
47	Labour for boring tube of required dia by water jet system through any type of soil strata including higher and labour charges for boring pipes, scaffolding tools and plants necessary and taking out them and lowering pipes, stainer, blind pipe etc. and fitting and fixing the same complete including bucket washing and others incidental works in this connection. The tube well should have a minimum 50mm gap in between the outside of the tube well pipe and the bore a) For depth up to 50 meter for 80m dia tube well	51	mtr	Rs.197.00	10047.00
48	Supplying fitting and fixing steel cutter up to 450mm length with socket. a) 100mm	1	Each	Rs.403.00	403.00
49	Supplying, fitting and fixing plug of approved make conforming to I.S.specifications	1	Each	Rs.130.00	130.00
50	Supply of 100m dia M.S. clamp	2	set	Rs.250.00	500.00
51	Supplying wasted pea size granules and packing the same around the bottom pipe up	2	cum	Rs.2,029.00	4058.00
52	Supply of fitting fixing of 100mm dia G.I. cap....	1	Each	Rs.139.00	139.00
53	Supply of fitting fixing of 32mm dia G.I. Bend....	1	Each	Rs.154.00	154.00
54	Supply and delivery of PVC threaded pipes for sinking of I.M. II - Tube well conforming to ASTM-D-1785 (Schedule 80 medium duty) to match with G.I. pipes as per I.S.-1239(part-I) and threads as per IS-55411985 identical with ISO 711-1982 (Part -I) inclusive of all tunes other incidental charges if any including carrying to the store loading, uploading and stacking properly etc all complete as per direction of the EIC (Each pipe will have one socket fitted).				
	ii) 80 mm dia	45	M	Rs.407.00	18315.00
	iii) 32mm dia with hanging pipe	39	M	Rs.169.00	6591.00
55	Supplying PVC strainer of approved make with adapter conforming to I.S.12818 specifications. 80mm dia	6	M	Rs.492.00	2952.00
56	Supply installation and commissioning of electricity operated (220V) submersible				
	a) 1.0 H.P. Pump MORTOR SET (Crompton greaves/KSB/kilosker)	1	L.S.	Rs.10,000.00	10000.00
57	Supply & delivery at site 2.5mm, 3 core water proof flat cable suitable for above submersible pump & motor (panel finolex/neteo/emgee)	80	M	Rs.64.00	5120.00
TOTAL					339313.00
Add CGST 6%					20359.00
Add SGST 6%					20359.00
Total					380031.00
Add Cess @1%					3800.00
Grand Total					383831.00

Rupees three lakh ninety five thousand two hundred thirty two only


Executive Officer
Nanor Panchayat Samity
Nanor::Birbhum



Junior Engineer
Nanor Development Block
Nanor::Birbhum


Schedule for SI no -03

Schedule Construction of Concrete road at SI of School , Basapara of Thupsara GP within Nanoor Panchayat Samity under head 15th CFC

SI no	Description of Items	Total Quantity	Unit	Rate (in Rs.)	Amount (in Rs.)
1	Box cutting or filling in road embankment in all sorts of soil in/c spreading the spoils properly over the flank as necessary or on berm to approximate grade camber and soiling the sub-grade with power rolled as per direction (depth upto 15cm)	216.00	sqm	Rs. 14.40	3110.00
2	Sand filling in foundation trenches and at the back of abutment, wing walls etc. with good local sand free from earth in layers not exceeding 15cm including inundating each layer by profuse water and poking and ramming layer by layer complete	26.33	cum	Rs. 572.55	15075.00
3	Single layer BFS with picked jhama bricks and filling the joints with local sand.	216.00	sqm	Rs. 266.00	57456.00
4	Brick work with 1st class bricks in cement mortar 6:1(i) foundation and plinth	3.77	cum	Rs.4,198.04	15827.00
5	Plain cement concrete (1:2:4) with grade stone chips of appropriate nominal size including screening and cleaning course aggregate and coarse sand curing in water with cost and carriage of all materials but excluding cost of shuttering complete	52.65	cum	Rs. 4,671.13	245935.00
6	Hire and labour charges for side shuttering fitting, fixing all complete with prop	18.0	sqm	Rs. 93.00	1674.00
7	Providing Thermocol for expansion joint	10.80	sqm	Rs. 30.00	324.00
8	Plaster with cement sand mortar including rounding off corners or chamfering corners as directed and including racking out joints or roughening of concrete surface, curing without and carriage of all materials with (1:6) cement mortar.	38.53	sqm	132.54	5107.00
9	Galvanised corrugated iron sheet work (including the supporting frame work) fitted and fixed with 10 mm. dia J or L hook-bolts, limpet and bitumen washers and putty complete with 150 mm. end lap and one corrugation minimum side lap.(Payment to be made on area of finished work)(GCI sheet to be supplied by contractor)	135	sqm	Rs. 619.00	83565.00
Total					428073.00
Add CGST @ 6%					25684.00
Add SGST @ 6%					25684.00
Total					479441.00
Add Cess @ 1%					4794.00
Grand Total					484235.00

Rupees Four Lakh(s) Eighty Four Thousand Two Hundred Thirty Five Only


Executive Officer
Nanoor Panchayat Samity
Nanoor Birbhum


Sub Assistant Engineer
Nanoor Development Block
Nanoor Birbhum


Schedule for SI no -04

Schedule for construction of Community Hall at Madhudanga under Nanoor Panchayat Samity under head 15th CFC.

SI no.	Description of Items	Total Qnt.	Unit	Rate	Amount
1	Earth work in excavation in foundation trenches or drain in all sorts of soils (including mixed soil) the item includes necessary trimming the side of trenches leveling dressing and ramming the bottom, bailing out water as required complete. Depth of excavation upto 1.5 mtr	27.65	cum	Rs.119.27	3298.00
2	Filling in foundation or plinth by fine sand in layers not exceeding 1.5mm salutation with water ramming complete including the cost of supply of sand	28.25	cum	Rs.572.55	16175.00
3	Single layer brick flat soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints.	23.04	sqm	Rs.266.00	6129.00
4	Cement concrete with graded stone ballast(40mm size excluding shuttering) in ground floor (1:3:6)	9.49	cum	Rs.4,105.50	38961.00
5	Ordinary cement concrete with M20 grade (1:1.5:3) with graded stone chips 20mm down excluding shuttering and reinforcement at ground floor	29.69	cum	Rs.4,976.83	147762.00
6	Hire and labour charges for shuttering with centering and necessary staging upto 4m using approved props of slab beam column lintel curve or straight including fitting fixing and striking out after completion of works with Props in GF (i) Without props	87.50	sqm	Rs.205.00	17938.00
7	Hire and labour charges for shuttering with centering and necessary staging upto 4m using approved props of slab beam column lintel curve or straight including fitting fixing and striking out after completion of works with Props in G.F (ii) With props	126.69	sqm	Rs.328.00	41554.00
8	Brick work with 1st class bricks in cement mortar 6:1(ii) in superstructure in GF	2.19	cum	Rs.4,421.04	9682.00
9	Plaster (in wall, floor etc.) with sand and cement mortar including rounding off or chamfering corners as directed and racking out joints or roughening of concrete surface including throating, noising and drip courses where i) With 4:1 cement mortar 10mm thick in G floor	109.25	sqm	Rs.119.53	13059.00
10	Plaster (in wall, floor etc.) with sand and cement mortar including rounding off or chamfering corners as directed and racking out joints or roughening of concrete surface including throating, noising and drip courses where iii) With 1:6 cement mortar 15mm thick in Ground floor	46.40	sqm	Rs.132.53	6149.00
11	Neat cement punning on plaster surface	12.80	sqm	Rs.32.74	419.00
12	Reinforcement for reinforced concrete work in all sorts of structure in/c distribution bars, stirrups, binders etc. in/c supply of rods, initial straightening and removal of loose rust (if necessary) cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (JSW/JSP/LSHYAM/SRMB/ELECTROSTEEL/BMASL/SSL)	1.86	MT	Rs.53,015.07	98608.00
13	Artificial stone in floor, dado, stair case etc. with cement conc. (4:2:1) with stone chips laid in panels as directed with topping made with ordinary or white cement and marble dust in proportion 2:1:1 in/c smooth finishing and rounding off corners and in/c application of cement sluvy before fore flooring works using cement @ 1.75Kg/Sqm all complete in/c all materials and	109.25	sqm	Rs.239.77	26195.00
14	White washing with any shed with strainer as required including cleaning and smoothening the surface thoroughly.	155.65	sqm	Rs.20.01	3115.00
Total					429044.00
Add CGST @6%					25743.00
Add SGST @6%					25743.00
Total					480530.00
Add Cess @ 1%					4805.00
Grand Total					485335.00

Rupees Four Lakh(s) Eighty Five Thousand Three Hundred Thirty Five Only


 Executive Officer
 Nanoor Panchayat Samity
 Nanoor :: Birbhum


 Junior Engineer
 Nanoor Development Block
 Nanoor :: Birbhum